



ADDENDUM NO. 1 TO THE BID DOCUMENTS FOR:

**Manhole Repair Project 2024
Capital Project #24WW01**

Date of Addendum: June 7, 2024

Original Bid Due Date/Time: June 10, 2024 - 4:00PM Local Time

New Bid Due Date/Time: June 17, 2024 - 4:00PM Local Time (1-week extension)

Previous Addenda: None

To: Prospective Bidders:

This Addendum forms part of the “Contract Documents” and modifies or clarifies the original “Contract Documents” for this Project dated May 17, 2024. Prospective Bidders **shall** acknowledge receipt of the total number of Addenda issued for this Project on Pages 1-3 and 1-5, Sections 1.2 and 1.3 of the Bid Document.

Item 1:

In response to questions received from prospective bidders, the specifications have been amended to include the following two points, in addition to the original text:

- PRV vault spraying shall exclude floors of the vaults.
- Chemical grout injecting is considered a sub task of spraying and does not have a standalone bid item. Any cost associated with chemical grout injection shall be factored into the cost for spraying bid items.

Attachments – B.1 Addendum 1 of the Bid Package

End of Addendum 1

Dated: 6/7/24

Mammoth Community Water District

By: David Carlson

David Carlson
Associate Engineer

Attachment B.1 Addendum 1

Manhole Repair Project 2024

Specifications

- Traffic control shall be performed as necessary by the contractor. Traffic control shall follow TOML or Caltrans standards based on location.
- The contractor shall determine when bypassing of sewer flows is required and perform that bypass using above ground pumps and hoses.
- Follow confined space entry procedures per Cal/OSHA standards.
- Complete necessary preparation work including but not limited to removal of roots, grease removal, rebar installation, chemical grout injection, and cleaning of adhesion areas.
- Any manholes that have existing ladder rungs will need the rungs removed prior to spraying.
- Base reconstruction will be done in such a manner which will maximize effective flow characteristics and fully open channels allowing for access of maintenance equipment.
- Spraying shall include base, barrel, and cone.
- All water infrastructure in the PRV vaults shall be protected from damage from equipment and spray.
- PRV vault spraying shall exclude floors of the vaults.
- Chemical grout injecting is considered a sub task of spraying and does not have a standalone bid item. Any cost associated with chemical grout injection shall be factored into the cost for spraying bid items.